## MYSORE DIVISION.

*Dated 12th February* 1913.

Notice is hereby given that sealed tenders will be received at the Office of the Executive Engineer, Mysore Division, up to 15th March 1913, for improving the roof of Sandalkoti at Hunsur. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1914.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's Office at Mysore, between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees three hundred (300) in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for improving the roof of Sandalkoti at Hunsur," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with Chief Engineer, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's Office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Improving the roof of Sandalkoti at Hunsur.

| No. | Items of work | Per | Quantity |
|---|---|---|---|
| 1 | Removing the existing roof of pan tiles and bamboo sticks, etc. | Sq. | 274·20 |
| 2 | Teakwood work wrought and put up ... ... | C. ft. | 213·68 |
| 3 | Roofing with 1st class Mangalore tiles, teak reepers, etc., complete. | Sq. | 274·20 |
| 4 | Mangalore ridge tiles set in mortar and cement pointing ... | R. ft. | 1,240 |
| 5 | Reconstructing the top of walls with burnt brick in chunam | C. ft. | 3,088 |
| 6 | Chunam plastering ... ... ... ... | Sq. | 477·84 |
| 7 | White and colorwashing ... ... ... | Do | 477·84 |
| 8 | Flooring with gravel and tamping ... ... ... | C. yd. | 149 |
| 9 | Removing the existing earth flooring and make it one uniform level. | Sq. | 40·31 |
| 10 | Inserting new teakwood work in place of rotten ones during execution. | Lump | sum. |

R. V. SUNDARAM IYER,
*Executive Engineer.*

## MYSORE CITY IMPROVEMENT TRUST BOARD.

FORM OF ADVERTISEMENT.

*Dated 3rd March* 1913.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, City Improvements Division, up to 10th and 17th March 1913, for improving the surroundings of Curzon Park, Mysore. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of May 1913.